

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970
 Luce Co. Three Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. <u>47</u> N. R. <u>11</u> W.	K-9 L-9 L-8
2. PROPERTY CONTROLLING IN SECTION.....	T. _____ N. S., R. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. _____ N. S., R. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 12-12 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- K-9 Sec. Cor. 23-24-25-26, set by Geo. H. Cannon, D.S. 1853.
Bearings were: Beech 10", N53°W, 25 lks. and Beech 12", S65°E, 45 lks.
- L-9 Quarter Cor. bet. Sec's. 24-25, set by Geo. H. Cannon, D.S. 1853.
Bearings were: Maple 16", N47°E, 26 lks. and Y. Birch 14", S40°W, 15 lks.
- L-8 Center Corner, Section 24.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- K-9 Corner re-established by Double Proportionate Measure.
No evidence of original corner.
- L-9 Corner re-established midway and on line bet. two Sec. Cors.
- L-8 Corner placed at intersection of lines, connecting opposite Quarter Corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Placed 1" pipes with 4" aluminium caps at all corners.

- K-9 New Bearings: 12" W. Pine, S58°E, 82.3' and 6" R. Pine, S82°W, 17.6'
- L-9 New Bearings: 7" R. Pine, N57°E, 47.4' and 7" W. Pine, N21°E, 32.7'
- L-8 New Bearings: 10" W. Pine, S11°W, 25.3' and 6" W. Pine, N24°E, 17.6'

SIGNED BY Billy D. Buckler DATE 2-4-74

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR