

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
 Luce Co. Three Corners

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. _____ E. _____ S., R. _____ W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>24</u>	, T. <u>47</u> N. _____ E. _____ S., R. <u>11</u> W.	<u>5-Sec. 24</u> <u>9-Sec. 24</u> <u>6-Sec. 24</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ E. _____ S., R. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 12-11 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 5-Sec. 24 North 1/16 Corner, Section 24.
- 9-Sec. 24 East 1/16 Corner, Section 24.
- 6-Sec. 24 North-East 1/16 Corner, Section 24.


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 5-Sec. 24 Placed 1/16 Corner, midway between $\frac{1}{4}$ Cor. to North and Center Corner to South.
- 9-Sec. 24 Placed 1/16 Corner, midway between $\frac{1}{4}$ Cor. to East and Center Corner to South.
- 6-Sec. 24 Placed 1/16 Corner at intersection of lines, quartering the North-East Quarter Section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Placed 1" pipes with 4" aluminium caps at all corners.
- 5-Sec. 24 Bearings: 10" Twin W. Pine, N37°E, 44.2' and 10" W. Pine, N19°W, 35.0'
 - 9-Sec. 24 Bearings: 10" W. Pine, N81°E, 13.3' and 10" W. Pine, S28°W, 30.4'
 - 6-Sec. 24 Bearings: 12" W. Pine, S50°E, 34.0' and 6" W. Pine, N27°W, 12.4'

SIGNED BY Billy D. Buckler DATE 2-4-74
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR