

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

Two Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>47</u> ^{N.} S. , R. <u>11</u> ^{X.} W.	<u>I-5</u>
2. PROPERTY CONTROLLING IN SECTION <u>13</u>	T. <u>47</u> ^{N.} S. , R. <u>11</u> ^{X.} W.	<u>3-Sec.13</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} S. , R. _____ ^{E.} W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on 2-14 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

3-Sec.13 North 1/16 Corner, on Westside of Section 13.

I-5 Sec. Cor. 10-11-14-15, set by Geo. H. Cannon D.S. 1853.
Bearings were: Beech 9", N50°, 25 lks. and Beech 16", S45°E, 54 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

3-Sec.13 Corner placed midway bet. Sec. Cor. to North and 1/4 Cor. to South.

I-5 Corner placed at an old wood post, set by unknown Surveyor. Located in line with a road to West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with Dep't cap at both corners.

3-Sec.13 Bearings are: 16" Hemlock, East, 39.4' and 8" Spruce, N70°W, 1.0'


I-5 New Bearings: 8" Red Pine, S70°E, 10.3' and 10" Red Pine, S67°W, 20.9'

SIGNED BY _____

Billy D. Buckler
Billy D. Buckler

DATE 2-22-74

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____

CHIEF OF SURVEY PARTY

DATE _____

APPROVED AND SIGNED BY _____

MICHIGAN REGISTERED LAND SURVEYOR

DATE _____

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FORM NO. M-10735
REVISED 1974

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
DISTRIBUTED BY MICHIGAN SOCIETY OF REGISTERED LAND SURVEYORS