

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

Three Corners.

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>47</u> N. <u>X</u> , R. <u>11</u> W. <u>X</u>	K-5 K-4 L-5
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on 2-14 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:  
Corners originally set by Geo. H. Cannon, D.S. in 1853.

- K-5 Section Corner - 11,12,13,14.  
Bearings were: Sugar 15", N64°W, 20 lks. and Hemlock 16", S35°E, 37 lks.
- K-4 1/4 Corner bet. Secs - 11,12.  
Bearings were: Sugar 8", S80°E, 21 lks. and Beech 10", S60°W, 26 lks.
- L-5 1/4 Corner bet. Secs - 12,13.  
Bearings were: Beech 12", S55°E, 30 lks. and Beech 10", N44°W, 45 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- K-5 Corner re-established by Single Proportionate Measure, bet. Cors; 1 mile North and 1/2 mile South.
- K-4 Corner re-established by Single Proportionate Measure, bet. Cors; 1/2 mile North and 1 1/2 miles South.
- L-5 Corner re-established midway and on line bet. two section corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Placed 1" pipes with 4" aluminium caps or brass caps at all corners.

- K-5 New Bearings: 18" Maple, N85°W, 7.1' and 20" W. Pine, S59°E, 59.0'
- K-4 New Bearings: 12" twin Maple, S85°E, 104.4' and 26" W. Pine Stump, N15°W, 70.7'
- L-5 New Bearings: 8" R. Pine, S5°E, 64.8' and 8" R. Pine, N10°E, 119.0'

SIGNED BY Billy D. Buckler DATE 2-22-74

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_