

# LAND CORNER RECORDATION CERTIFICATE

**FILING REQUIREMENT OF ACT 74, MICH. P.A.1970**

Luce Co.

4 Corners.

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. S., R. _____ E. W.	7-Sec.34 _____ 5-Sec.34 _____
2. PROPERTY CONTROLLING IN SECTION <u>34</u>	T. <u>47</u> N. S., R. <u>11</u> E. W.	5A-Sec.34 _____ 7A-Sec.34 _____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 9/16-23/, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 7-Sec.34 North 1/16 Corner, on Eastside of Section 34.
- 5-Sec.34 North 1/16 Corner, Section 34.
- 5A-Sec.34 Meander Corner on North 1/16 line, and on Westside of Wolverine Lake.
- 7A-Sec.34 Meander Corner on North 1/16 line, and on Eastside of Wolverine Lake.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 7-Sec.34 Corner placed midway between  $\frac{1}{4}$  Corner to South and Section Corner to North.
- 5-Sec.34 Corner placed midway between  $\frac{1}{4}$  Corner to North and Center Corner to South.
- 5A-Sec.34 Corner placed on West edge of lake, 1,025.7' East of the North 1/16 Corner.
- 7A-Sec.34 Corner placed on East edge of lake, 718.0' West of the North 1/16 Corner, on Eastside of Section 34.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with 4" aluminium cap at all corners.

- 7-Sec.34 No witnesses available. Corner lies on West edge of a N-S plantation road.
- 5-Sec.34 Bearings: 14" W. Pine, S56°W, 30.2' and 14" W. Pine, N61°W, 41.3'.
- 5A-Sec.34 Bearings: 10" W. Pine, N89°W, 100.4' and 8" W. Pine, N50°W, 70.4'.
- 7A-Sec.34 Bearings: 12" W. Pine, N89°E, 26.1' and 18" W. Pine, N23°W, 61.3'.

SIGNED BY Billy D. Buckler  
 Billy D. Buckler  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

DATE 9-8-78



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
 APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_