

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

LUCE CO.

| FOR CORNERS OF-- | LOCATED IN-- | CORNER CODE NUMBER |
|---|---|--------------------|
| 1. PUBLIC LAND SURVEY----- | T. <u>47</u> N. <u>X</u> R. <u>11</u> W. | J-7 |
| 2. PROPERTY CONTROLLING IN SECTION----- | T. _____ N. _____ S. R. _____ E. _____ W. | _____ |
| 3. MISCELLANEOUS PROPERTY IN SECTION----- | T. _____ N. _____ S. R. _____ E. _____ W. | _____ |
| 4. LOT NO. _____, RECORDED PLAT----- | _____ | _____ |
| 5. PRIVATE CLAIMS----- | _____ | _____ |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 6-27, 1989, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

J-7 North 1/4 of Section 23. Corner set by Billy D. Buckler L.S. in 1961.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

J-7 Moved this corner as recorded by Billy D. Buckler L.S. in 1961 (L.S. # 8887). Found this corner was set 151.4' West and 67.7' North of a single proportionate measure between Section Corners 1/2 mile East and West. Measurement East to a small pond is long by same amount. Could not find any evidence of original Hemlock stumps at either location. Also a note in Billy D. Bucklers files, dated 1973, stating this corner should be moved 155' East and 58' South of his recorded position, corner was never moved.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-7 DNR Monument

14" W. Pine, N37°W, 238.3' and 10" Cherry, N27°W, 47.4' and 8" W. Pine, N32°E, 291.0' and 36" W. Pine Stump, N63°E, 35.5'.

SIGNED BY Gerald L. Wiggins DATE 10-9-89

SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET