

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<b>LUCE</b>	(County)	Located In:	Corner Code #/
1. Public Land Survey		T 47N R 11W	I-6
		T R	
		T R	
2. Property Controlling in Section	S 22	T 47N R 11W	1
	S 22	T 47N R 11W	3
3. Miscellaneous Property in Sec	S 22	T 47N R 11W	4
	S	T R	

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat  
 5. Private Claims

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6													
7	16	17	18	19	20	21	22	23	24				
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, **GERALD L. WIGGINS**, in a field survey on 7-10, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration.

- 1 West 1/16 Corner on North side of Section 22. Not previously set.
  - 3 North 1/16 Corner on West side of Section 22. Not previously set.
  - 4 N.W. 1/16 Corner of Section 22. Not previously set.
- I-6 East 1/4 Corner of Section 15. Corner set by Billy D. Buckler, L.S. 5-16-73. 15" W. Spruce, S52°W, 46.9' and 5" S. Maple, S88°W, 9.6'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

- 1 Corner set midpoint on line between N.W. Corner and North 1/4 Corner of Section 22.
  - 3 Corner set midpoint on line between N.W. Corner and West 1/4 Corner of Section 22.
  - 4 Corner set at intersection of N.W. 1/4 of Section 22 by closed traverse.
- I-6 Buckler's Spruce witness has been cut and 5" Maple is now a 8" Maple.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.  
**D.N.R. MONUMENT AT ALL THREE CORNERS.**

- |                             |                            |                            |
|-----------------------------|----------------------------|----------------------------|
| 1 26" W. Pine, S87°E, 32.9' | 3 8" W. Pine, S34°W, 16.7' | 4 12" W. Pine, S68°E, 5.3' |
| 10" W. Pine, S27°E, 47.6'   | 18" W. Pine, N50°W, 27.9'  | 10" W. Pine, S45°W, 22.0'  |
| 8" W. Pine, S34°W, 44.6'    | 12" Spruce, N03°E, 61.7'   | 20" W. Pine, N80°W, 28.45' |
| 10" Balsam, N04°E, 12.65'   | 16" W. Pine, S31°E, 29.9'  | 10" W. Pine, N46°E, 18.2'  |
- I-6 6" Twin Spruce, N30°W, 61.8'  
 14" W. Pine, S4°E, 31.3'  
 5" Hemlock, North, 43.1'  
 Buckler's 8" Maple, S88°W, 9.6'

Signed by Gerald L. Wiggins Date 10-9-89  
 Surveyor's Michigan License No. 23521

