

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

LUCE CO.

2 CORNERS

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. _____ N. _____ S. R. _____ E. _____	_____
2. PROPERTY CONTROL- ING IN SECTION 25, T. 47, N. _____ S. R. 11, E. _____	_____	2, 9
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. _____ S. R. _____ E. _____	_____	_____
4. LOT NO. _____, RECORDED PLAT _____	_____	_____
5. PRIVATE CLAIMS _____	_____	_____

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 1-25, 1988, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 2 East 1/16 Corner on Northside of Section 25. Not previously set.
- 9 East 1/16 Corner of Section 25. Not previously set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 2 Corner set midpoint on line between the North 1/4 Corner and North east Section Corner of Section 25.
- 9 Corner set midpoint on line between the East 1/4 Corner and computed Center Corner of Section 25 by closed traverse.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D.N.R. Monument set at both corners.

- | | |
|-------------------------|---------------------------------|
| 2 1" Pipe, S40°E, 3.41' | 9 Twin 12" Maples, S83°E, 12.3' |
| 8" Maple, S13°E, 28.0' | Twin 6" Maples, N52°E, 12.2' |
| 4" Maple, S13°W, 25.3' | 12" Jack Pine, N62°W, 36.1' |
| 5" Maple, N70°W, 20.8' | 1" Iron Pipe, S11°W, 6.89' |


SIGNED BY Gerald L. Wiggins DATE 2-3-88

SURVEYOR'S MICHIGAN REGISTRATION NO. 25351

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
REVISED MAY 14, 1975

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET