

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 47. NR. 12 W..

----- Luce ----- COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 19, 20, 29, 30.

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 20" White Pine Stp. N 25° W 60 links

40" White Pine Stp. (fragment) N 70° E 11 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced Section Corner from two White Pine B.T.'s in poor condition, burned.

Corner found while checking random lines with Bernard McTiver, District Forester.

Corner lies 42 links South and 57 links East of 78.62 ch. marker from West.

Corner placed and witnessed June 15, 1956.

SURVEYORS SEAL

SIGNED

*Billy D. Buckles*  
REGISTERED LAND SURVEYOR

DATE 6/21/56