

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 16-47 NR 12-13 W.

... Luce and ~~Argon~~ *Schulcraft* ... COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 31, 6, 1, 36 on
township corner

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 36" W. Pine Stub S 56° E 242 links

30" W. Pine Stub S 5° W 188 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

No evidence of original corner.

Re-established township corner by Double Proportionate Measure to good corners in four directions.

Corner placed and witnessed August 3, 1956.

SURVEYORS SEAL

SIGNED

Billy D. Buckles
REGISTERED LAND SURVEYOR

DATE 8/17/56