

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Luce COUNTY
T 47N R 12W

DESCRIPTION OF CORNER Sec. cor. common to Secs. 28-29-32-33

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 7-2-71

WITNESSES TO CORNER..... 4" W. Pine (NBT) S16°E 31.7'



AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established by proportionate measure; from $\frac{1}{4}$ corner $\frac{1}{2}$ mile east;
Sec. cor. 1 mile west and by record distance from a pine line tree 9.63 chs.
south. Found no evidence of corner or witnesses.

SURVEYOR'S SEAL

SIGNED

Billy E. Buckler
Billy E. Buckler

DATE

8-18-71

REGISTERED LAND SURVEYOR

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68