

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Luce COUNTY  
T 47N R 12W

DESCRIPTION OF CORNER 1/4 Cor. bet. Secs. 28-33

CORNER MONUMENT 1" pipe with 1/4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 7-2-71

WITNESSES TO CORNER..... 9" Jack Pine (1/2S NBT) N64°W 39.0'



4" Jack Pine (NBT) S 38°E 16.0

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from remains of two probable witnesses, which were pine stump bottoms in proper position. Found original line trees, 9.66 chs. east and 8.80 chs. west of this corner.

SURVEYOR'S SEAL

*Billy D. Buckler*

DISTRIBUTION:

SIGNED Billy D. Buckler DATE 8-17-71  
REGISTERED LAND SURVEYOR

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68