

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Luce COUNTY  
T 47N R 12W

DESCRIPTION OF CORNER ‡ Cor. bet. Secs. 21-28

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 6-25-71

WITNESSES TO CORNER..... 5" W. Pine (‡S NBT) N35°W 3.8'



9" W. Pine (‡S NBT) N16°E 27.8'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from a W. Pine stump bottom, bearing S60°W, 35 links. Found no marks to identify this as a recorded witness but found corners to East and West. Proportionate measure falls close to this location. Distance East (525.0') to top of a high bank as well as a stream (1208') checks with record.

SURVEYOR'S SEAL

SIGNED *Billy E. Buckler*  
Billy E. Buckler  
REGISTERED LAND SURVEYOR

DATE 9-30-71

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing