

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Luce COUNTY
T 47N R 12W

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 17-18-19-20

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 5-25-71

WITNESSES TO CORNER..... 8" W. Pine (S18 NBT) N60°W 57.4'



10" W. Pine (S20 NBT) S10°E 75.3'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established by single proportionate distance from corners, $\frac{1}{2}$ mile north and $\frac{1}{2}$ mile south and on a bearing indicated by the record notes.
Found no evidence of the original corner or witnesses.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler

Billy D. Buckler

DATE

9-30-71

DISTRIBUTION:

REGISTERED LAND SURVEYOR

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68