

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Luce COUNTY  
T 47N R 12W

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 29-30-31-32

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 4-23-71

WITNESSES TO CORNER..... 6" W. Pine (S30 NBT) N67°W 10.2'



8" Jack Pine (S29 NBT) N78°E 40.8'

9" Jack Pine (S31 NBT) S2°W 53.5'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established on line and by proportionate distance between Sec. Cor. one mile South and Sec. Cor. one mile North.

The original corner was placed on a straight, three mile line.

Found an original line tree on the mile to North, conforming to this location.

SURVEYOR'S SEAL

SIGNED

*Billy D. Buckler*  
Billy D. Buckler

DATE

9-28-71

REGISTERED LAND SURVEYOR

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68