

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Luce COUNTY
T 47N R 12W

DESCRIPTION OF CORNER 1/2 Corner bet. Secs. 29-30

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 4-23-71

WITNESSES TO CORNER..... 8" Jack Pine (1/2 S NBT) N32°E 1.7'



9" Jack Pine (1/2 S NBT) S17°E 28.6'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established midway and on line bet. two Sec. Cors. Found no evidence of the original corner.
Found an old down pine with blaze to south of this corner, which I believe to be on the original random line, which was a 3-mile random.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Billy D. Buckler
Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE

9-30-71

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68