

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

J

Luce COUNTY


T 47N R 12W

DESCRIPTION OF CORNER ¼ Cor. bet. Sess. 19-20

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 5-25-71

WITNESSES TO CORNER..... 5" Jack Pine (½S NBT) N58°W 12.8'



12" Jack Pine (½S NBT) N23°E 39 .2'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from remains of two original witnesses; a W. Pine stump, bearing N48°E, 08 links and a W. Pine stump, bearing S31°W, 17 links. Both stumps show evidence of a blaze and notch. Found an old post at this corner.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler
Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE

9-30-71

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68