

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Luce

(County)	Located in:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>11W</u>	<u>I12</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>34</u> T <u>47N</u> R <u>11W</u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

7 Aug 11 2003  
I12 Aug 05 2003

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:  
(I12) Quarter corner common to Sections 34-35. Reestablished in 1978 by Billy D. Buckler RLS midway and on line between Section corners.  
(7-Sec. 34) North 1/16 corner between Sections 34-35. Established in 1978 by Billy D. Buckler midway and on line between I11 and I12.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
(I12) The 1978 position for this corner is not correct. It was based on an erroneous position for the corner I13. Removed the 1978 monument for I12 and placed a new monument at the proper corner position, midway and on line between I11 2665.47' north and the corrected I13 2665.47' south. The corner monumented lies on the west side of a trail, in line with the edge of a J.Pine plantation to the east.  
(7-Sec. 34) The 1978 position for this corner is not correct. It was based on an erroneous position for the corner I12. I removed the 1978 monument for this 1/16 corner and established the corner midway and on a straight line between I11 and the corrected I12, 1332.73' north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
(I12) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:  
5" W.Pine S51W 55.75' "1/4S NBT"  
8" J.Pine N80E 18.1' do  
6" J.Pine N49E 23.55' do  
6" J.Pine N22E 49.3' do  
Bearings are magnetic. Distances are to nail with tag.  
(7) Set 1"ID I.pipe with 4" alum. cap (the 1978 monument). Blazed, scribed, and set measuring nails in:  
6" J. Pine S60E 25.15' "N1/16 BT"  
8" J. Pine N85E 21.3' do  
8" J. Pine N47E 22.4' do  
6" J. Pine N30E 55.9' do  
Bearings are magnetic. Distances are to nail with tag. Old squared wood post was set adjacent.



Signed by Stephan J. Szyszkoski Date 8/25/03  
Surveyor's Michigan License No. 33986