

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T 47N R 11W	H12	
	T R		
	T R		
	T R		
2. Property Controlling in Section	S 34 T 47N R 11W	9	
	S T R		
3. Miscellaneous Property in Sec.	S T R		
	S T R		

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Aug 11 2003

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
 (H12) Center of Section 34. Established in 1978 by Billy D. Buckler RLS, at the intersection of 1/4 lines.  
 (9-Sec. 34) East 1/16 corner, Sec. 34. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 (H12) The 1978 position for this corner is not correct. It was based on an erroneous position for the Quarter corner to the east, I12. I removed the 1978 monument and established the proper Center of Section at the intersection of straight lines connecting opposite 1/4 corners, using the corrected position for the Quarter corner I12. From the corner monumented, the center of a trail is approx. 20' South.  
 (9-Sec. 34) Established the corner midway and on a straight line between Center of Section 1323.12' West and Quarter corner (as recorded this date by the undersigned) 1323.12' East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 (H12) Set 1"IDx36" I.pipe with plastic cap stamped "MICH DNR PS 33986", projecting 12" above ground. Blazed, scribed, and set measuring nails in:  
 12" W.Pine N51E 16.5' "CS"  
 10" W.Pine N20E 3.0' "CS BT"  
 8" W.Pine S56E 9.35' do  
 6" W.Pine S39E 17.65' do  
 Bearings are magnetic. Distances are to nail with tag.  
 (9) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:  
 16" W.Pine N74W 6.7' "E1/16 BT"  
 8" W.Pine S77E 12.35' do  
 12" W.Pine N35E 29.9' do  
 24" W.Pine S42W 17.6' do  
 Bearings are magnetic. Distances are to nail with tag. Set cedar post adjacent.



Signed by Stephan J. Szyszkoski Date 8/25/03  
 Surveyor's Michigan License No. 33986