

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Luce

(County)

Located in:

Corner Code #

**1. Public Land Survey**

T R  
T R  
T R  
T R

**2. Property Controlling in Section**

S 34 T 47N R 11W 6

**3. Miscellaneous Property in Sec.**

S T R  
S T R

**4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_**

**5. Private Claims \_\_\_\_\_**

Aug 06 2003

1. Stephan J. Szyzkoski, in a field survey on 20 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

A. Description of original monument and accessories and/or subsequent restoration:  
 (6) NE 1/16 corner, Section 34, 1978: Established by Billy D. Buckler RLS at intersection of 1/16 lines. Mr. Buckler's witness corners on the east and west sides of Wolverine Lake, in which this corner falls.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 (6) Recovered the 1978 witness corners but did not accept the 1978 position for this 1/16 corner. The 1978 position was determined by a section subdivision which was based on an erroneous location for 112. Reestablished the corner at the intersection of straight lines connecting opposite 1/16 corners, after correcting 112. Placed witness corners on the 1/16 lines East 594.50', West 297.52', and South 388.48' from the position thus established. Witnesses to these three corners are shown below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(6) Set 1" IDx36" I-pipe with 4" alum. MONR cap on the 1/16 line 297.25' west of the position for this corner. Blazed, scribed and set meas. nails in:  
 16" M. Pine N82W 100.65 "8T"  
 14" M. Pine N52W 68.95' do  
 8" J. Pine N07W 9.7' do  
 5" J. Pine S57W 27.15' do  
 Edge of water approx 150' East. Bearings are magnetic. Dist. to nail with tag.

Set 1" IDx32" I-pipe with 4" alum. MONR cap on the East 1/16 line and 388.48' south of the position for this corner. Blazed, scribed, and set meas. nails in:  
 4" M. Birch S25E 15.45' "8T"  
 8" Spruce S22W 21.6' (slope) do  
 20" M. Pine S38W 23.8' (slope) do  
 thin 12" M. Pine S88W 37.85' (slope) do  
 Cedar post adjacent. Brgs magnetic. Distances to nail with tag. Water's edge 12' north.

Set a 1" ID I-pipe with 4" alum. cap on the North 1/16 line 594.50' East of the position for this corner. Blazed, scribed and set measuring nails in:  
 30" M. Pine N14W 53.5' (a 1978 8T)  
 20" M. Pine N74E 35.0' (slope) do  
 20" M. Pine N24E 50.35' do "8T"  
 18" M. Pine S82E 37.4' do do  
 35" M. to water's edge. Brgs magnetic. Distances to nail with tag. 16'E. to trail rd. c/l

Signed by Stephan J. Szyzkoski Date 8/25/03  
 Surveyor's Michigan License No. 33986

Register of Deeds Stamp & File Number