

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>47N</u> R <u>11W</u>	<u>J8</u>	
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
2. Property Controlling in Section	S <u>23</u> T <u>47N</u> R <u>11W</u>	<u>9</u>	
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

May 08 2007

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (J8) Center of Section 23. Not established in the original survey.
- (9-Sec. 23) East 1/16 corner, Section 23. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (J8) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.
- (9-Sec. 23) Established the corner midway and on a straight line between Center of Section 23 1322.48' west and Quarter corner 1322.48' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|--|
| (J8) Set 1"IDx36" I.pipe with 4" alum.
MDNR cap. Set measuring nails in: | (9) Set 1"IDx36" I.pipe with 4" alum.
MDNR cap. Set measuring nails in: |
| 12" J.Pine N23W 5.68' mrkd "CS BT" | 5" W.Pine S14W 10.6' mrkd "E1/16 BT" |
| 12" J.Pine N72W 14.16' do | 8" W.Pine N11E 28.65' do |
| 12" J.Pine S11W 10.0' do | 5" W.Pine N89W 12.21' do |
| 11" J.Pine S53E 43.2' do | 6" Cherry S68E 12.61' do |
| Bearings are magnetic. Distances are to nail with MDNR tag. | Bearings are magnetic. Distances are to nail with MDNR tag. |

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/7/07

For the Michigan Department of Natural Resources, Office of Land and Facilities