

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T _____ R _____		
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S <u>23</u> T <u>47N</u> R <u>11W</u>		<u>2</u>
	S <u>23</u> T <u>47N</u> R <u>11W</u>		<u>5</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		

Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

May 08 2007

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


- (2-Sec. 23) East 1/16 corner between Sections 14 and 23. Not established in the original survey.
- (5-Sec. 23) North 1/16 corner, Section 23. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (2-Sec. 23) Established the corner midway and on the Section line between Quarter corner 1313.38' west and Section corner 1313.38' east.
- (5-Sec. 23) Established the corner midway and on a straight line between Quarter corner 1311.30' north and Center of Section 23 1311.30' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|---|
| (2) Set 1"IDx36" I.pipe with 4" alum.
MDNR cap. Set measuring nails in:
9" W.Pine S15E 27.8' mrkd "E1/16 BT"
12" W.Pine N25E 12.15' do
5" Maple S54E 25.35' do
10" W.Pine S38W 9.7' do
Bearings are magnetic. Distances are to
nail with MDNR tag. | (5) Set 1"IDx36" I.pipe with 4" alum.
MDNR cap. Set measuring nails in:
8" W.Pine N71E 2.78' mrkd "N1/16 BT"
8" J.Pine S35E 9.23' do
10" W.Pine S45W 21.29' do
8" J.Pine West 15.4' do
Bearings are magnetic. Distances are to
nail with MDNR tag. |
|---|---|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/7/07

For the Michigan Department of Natural Resources, Office of Land and Facilities