

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S <u>23</u> T <u>47N</u> R <u>11W</u>	<u>6</u>
	S <u>23</u> T <u>47N</u> R <u>11W</u>	<u>7</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

May 08 2007

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


- (6-Sec. 23) Northeast 1/16 corner, Section 23. Not established in the original survey.
- (7-Sec. 23) North 1/16 corner between Sections 23 and 24. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (6-Sec. 23) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.
- (7-Sec. 23) Established the corner midway and on the Section line between Section corner 1310.62' north and Quarter corner 1310.62' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|--|
| (6) Set 1"IDx36" I.pipe with 4" alum.
MDNR cap. Set measuring nails in:
13" W.Pine N15E 16.85' mrkd "NE1/16 BT"
6" W.Pine N81E 49.26' do
12" W.Pine N44W 7.77' do
10" W.Pine S12W 47.28' do
Bearings are magnetic. Distances are to nail with MDNR tag. | (7) Set 1"IDx36" I.pipe with 4" alum.
MDNR cap. Set measuring nails in:
4" W.Pine S48W 17.97' mrkd "N1/16 BT"
9" J.Pine N53E 28.28' do
6" W.Pine S52E 36.35' do
8" W.Pine N06E 15.21' do
Bearings are magnetic. Distances are to nail with MDNR tag. |
|---|--|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/7/07

For the Michigan Department of Natural Resources, Office of Land and Facilities