

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T _____ R _____		
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S <u>15</u> T <u>47N</u> R <u>11W</u>		H6
	S <u>15</u> T <u>47N</u> R <u>11W</u>		8
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		
4. Lot No. _____, Recorded Plat _____			
5. Private Claims			

Register of Deeds Stamp & File Number

1														
2	6	5	4	3	2	1								
3														
4	7	8	9	10	11	12								
5														
6	18	17	16	15	14	13								
7														
8	19	20	21	22	23	24								
9														
10	30	29	28	27	26	25								
11														
12	31	32	33	34	35	36								
13														

I, Stephan J. Szyszkoski, in a field survey on 8 06/30/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H6) Center of Section 15. 1973 - Billy D. Buckler RLS monumented the corner at the intersection of lines connecting opposite 1/4 corners. Set 1"x36" iron pipe with MDNR cap. 10" W.Pine N10 1/2 E 61.4', 14" B.Cherry N81E 26.8'. Corner lies 58' North of County Rd. 422.

(8-Sec. 15) West 1/16 corner, Section 15. 1973 - Billy D. Buckler RLS established the corner position midway between the Center of Section 15 and the W1/4 corner of Section 15. Set 1"x36" iron pipe with MDNR cap. 8" Maple N74W 29.0', 8" Maple S41 1/2W 41.2'. Corner lies 81.4' North of County Rd. 422.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H6) Found the 1973 monument in good condition. My measurements on this section lead me to conclude that Mr. Buckler erred in determining the intersection of 1/4 lines and thus incorrectly monumented the Center of Section 15 in 1973. Removed the 1973 monument and established the corner at the intersection of straight lines connecting opposite 1/4 corners. From the position thus established, the 1973 position is N60W 7.1' distant.

(8-Sec. 15) Found the 1973 monument in good condition. My measurements on Section 15 lead me to conclude that Mr. Buckler erred in his calculation of the subdivision of this Section which led to his monumentation of an incorrect position for this corner. Removed the 1973 monument and established the corner midway and on a straight line between 1/4 corner 1326.38' west and Center of Section 15 1326.38' east. From the position thus established, the 1973 position is N25W 6.6' distant.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H6) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 11" W.Pine S47W 19.1' mrkd "CS BT" 6" Maple N50W 20.3' do 6" Maple N25E 15.55' do 8" Balsam N82E 13.25' do Bearings are magnetic.	(8) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 6" Sugar N53E 3.65' mrkd "W1/16 BT" 6" Balsam S25E 9.95' do 8" Maple S56W 38.3' do 8" Sugar N86W 21.6' do Bearings are magnetic.
---	--

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 07/29/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities