

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>11W</u>	<u>15</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on 06/01/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(15) Corner common to Sections 10-11-14-15. 1854 - Established by Geo.H.Cannon Deputy Surveyor. Set post. Beech 9" N50W 25 links, Beech 16" S45E 54 links. 1974 - Remonumented by Billy D. Buckler RLS: "Corner placed at an old wood post, set by unknown Surveyor. Located in line with a road to West. Set 1" pipe with MI Dept. of Natural Resources cap. 8" Red Pine S70E 10.3', 10" Red Pine S67W 20.9'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(15) Found the 1974 monument in good condition and at record bearing and distance from the 1974 witnesses, both in good condition with overgrown blazes. Measured West 5299.2' (GLO = 5284.6') and South 2635.1' (GLO = 2640.0') to accepted corners. Accepted the monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(15) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 16" R.Pine S67E 10.9' mrkd "S14" 1974 NBT  
 17" R.Pine S70W 21.37' mrkd "S15" do  
 16" R.Pine N07E 60.71' mrkd "S11 NBT"  
 16" R.Pine N16W 47.2' "S10 NBT"  
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 07/29/2009  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities