

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 47N R 11W	G5
	T _____	_____
	T _____	_____
2. Property Controlling in Section	S _____	_____
	S _____	_____
	S _____	_____
3. Miscellaneous Property in Sec.	S _____	_____
	S _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5							●						
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 06/30/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(G5) Corner common to Sections 9-10-15-16. 1854 - Established by Geo.H.Cannon Deputy Surveyor during a correctional survey of this township. Set post. Beech 11" S61W 12 links, Sugar 9" N74E 32 links. Old Cor. Hemlock 14" N37E 30 links, Maple 15" S25W 20 links. (61 links S and 22 links W). 1970 - Remonumented by Billy D. Buckler RLS: "Corner replaced by measuring record distance from an older unacceptable corner which had been effaced by the Deputy Surveyor, Cannon. Found remains of possible Sugar bearing. Found the effaced Hemlock, 61 links South and 22 links West of corrected corner". Set 1" pipe with 4" aluminum cap. 8" Soft Maple N60W 8.9', 11" Hard Maple N74E 5.4'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(G5) Found the 1970 monument in good condition and at record bearing and distance from the 1970 bearing trees, both in good condition with overgrown blazes. Accepted the monument as a careful and faithful reestablishment of the position of the original corner. The effaced Hemlock mentioned in the record, now a 12' snag, is in place with blaze visible.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(G5) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 12" Maple N59W 9.2' mrkd "S9" 1970 NBT  
 16" Sugar N75E 5.25' "S10" do  
 14" Maple S67W 15.25' mrkd "S16 NBT"  
 17" Maple S18E 24.8' "S15 NBT"  
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 07/29/2009  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities