

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 47N R 11W	G6
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16	●	15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Stephan J. Szyszkoski, in a field survey on 06/30/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(G6) Quarter corner common to Sections 15-16. 1854 - Established by Geo.H.Cannon Deputy Surveyor midway and on the Section line between Section corners 40.00 chains north and south. Set post. Sugar 15" S10E 2 links, Sugar 8" N32W 19 links. ca. 1960 - Michigan DNR records by L. Rubick state: "Sq. post (new). Old sq. post down, Faced maple with writing and 1.5 ch. south is iron pipe". 1970 Remonumented by Billy D. Buckler RLS "at wood post, set by unknown surveyor. Distance south to a good corner is 2620.0'. Corner lies 102' North of an old road intersection." Set 1" pipe with 4" aluminum cap. 10" Hard Maple S55W 22.0', 9" Soft Maple S38E 15.7'. 1989 - Billy D. Buckler blazed top blazes on these NBTs, placed new post and location tag on tree south at road.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(G6) Found the 1970 monument in good condition and at record bearing and distance from the 1970 NBTs. The Hard Maple SW is in good condition. The Soft Maple SE is dead. The Section corner G7 was found 2619.87' South. The Section corner G5 was found 2670.24' North. Accepted the monument as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(G6) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 12" Sugar S58W 22.6' mrkd "1/4S" 1970 NBT  
 16" Sugar S55E 5.05' mrkd "1/4S NBT"  
 14" Sugar N73W 16.95' do  
 14" Sugar N03E 21.55' do  
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 07/29/2009  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities