

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T 47N R 11W	H5	
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5								●					
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 06/01/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H5) Quarter corner common to Sections 10 and 15. 1854 - Established by Geo.H.Cannon Deputy Surveyor midway and on the Section line between Section corners 40.035 chains east and west. Set post. Beech 14" S10W 19 links, Y.Birch 10" N50E 19 links. 1973 - Reestablished and recorded by Billy D. Buckler RLS midway and on line between Section corners. Set 1"x36" I.pipe with MI Dept. of Natural Resources alum. cap. 14" Maple S87E 43.9', 10" Maple S37W 40.8'. Corner lies 39.5' North of Murray Lake Rd.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H5) Found the 1973 monument in good condition and at record bearing and distance from the 1973 witnesses, both in good condition with overgrown blazes. The 1973 monument was found N71E 2.3' from the proportionate position described in the 1973 record and I accept same as a careful and faithful reestablishment of the position of the original corner. Left the monument in place and made new witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H5) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 18" clump Maple S82E 43.69' mrkd "1/4S" 1973 NBT
 16" Maple S41W 41.1' do do
 6" Cherry S50E 30.6' mrkd "1/4S NBT"
 5" W.Pine N70W 6.76' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 07/29/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities