

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 33 T 47N R 11W	6
	S 33 T 47N R 11W	9
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 6 07/24/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(6-Sec. 33) Northeast 1/16 corner, Section 33. Not established in the original survey.

(9-Sec. 33) East 1/16 corner, Section 33. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(6-Sec. 33) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

(9-Sec. 33) Established the corner midway and on a straight line between Center of Section 1319.84' west and Quarter corner 1319.84' east.


**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(6) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.  
 Set measuring nail with MDNR tag in the side of:  
 13" W.Pine N62W 6.72'                      mrkd "NE1/16 BT"  
 16" W.Pine S16E 13.2'                      do  
 8" W.Pine S30W 13.55'                      do  
 7" Spruce N68E 10.04'                      do  
 Bearings are magnetic.

(9) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.  
 Set measuring nail with MDNR tag in the side of:  
 9" Maple N45E 25.63'                      mrkd "E1/16 BT"  
 12" Maple N05E 15.52'                      do  
 20" Maple N75W 5.6'                      do  
 13" Maple S54E 8.49'                      do  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 09/09/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities

47108  
47109