

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S 33 T 47N R 11W	13	_____
	S 33 T 47N R 11W	16	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims			

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 13 07/24/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (13-Sec. 33) Southeast 1/16 corner, Section 33. Not established in the original survey.
- (16-Sec. 33) East 1/16 corner between Section 33 T47N-R11W and Section 4 T46N-R11W. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (13-Sec. 33) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.
- (16-Sec. 33) Established the corner midway and on the Township line between Quarter corner 1322.53' west and Section corner 1322.53' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|---|
| (13) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
12" Maple N56W 22.98' mrkd "SE1/16 BT"
10" Maple N51E 20.72' do
6" Maple S74E 15.86' do
8" twin Maple S21W 6.36' do
Bearings are magnetic. | (16) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
9" W.Pine S78E 18.1' mrkd "E1/16 BT"
8" W.Pine N15W 16.37' do
5" W.Pine N81W 9.18' do
18" W.Pine S06E 14.53' do
Bearings are magnetic. |
|---|---|

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 09/09/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities

47110
47111