

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T _____ R _____		
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S <u>33</u> T <u>47N</u> R <u>11W</u>		<u>12</u>
	S <u>33</u> T <u>47N</u> R <u>11W</u>		<u>5</u>
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 05/27/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (12-Sec. 33) South 1/16 corner, Section 33. Not established in the original survey.
- (5-Sec. 33) North 1/16 corner, Section 33. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (12-Sec. 33) Established the corner midway and on a straight line between Center of Section 33 1316.90' north and Quarter corner 1316.90' south. The position for the corner falls on the west side of N-S County Road #415.
- (5-Sec. 33) Established the corner midway and on a straight line between Center of Section 1319.35' south and Quarter corner 1319.35' north. The corner falls in the N-S County Road #415.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|---|
| <p>(12) Set 5/8"x24" rebar with plastic cap #33986
 Set measuring nail with MDNR tag in the side of:
 5" W.Pine N44W 42.05' mrkd "S1/16 BT"
 10" W.Pine S73W 53.1' do
 14" W.Pine S55E 52.9' do
 12" W.Pine N38E 77.2' do
 Bearings are magnetic.</p> | <p>(5) Set 5/8"x24" rebar with plastic cap #33986.
 Set measuring nail with MDNR tag in the side of:
 8" W.Pine N47W 66.52' mrkd "N1/16 BT"
 10" W.Pine S72W 45.9' do
 10" W.Pine N53W 51.3' do
 Found a 1.5" ID I.pipe N89E 23.86'
 Bearings are magnetic.</p> |
|---|---|

Signed by Stephan J. Szyszkoski Date 09/09/2008
 Surveyor's Michigan License No. 33986



For the Michigan Department of Natural Resources, Office of Land and Facilities