

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Lucas</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>12W</u>	<u>H1</u>
	T <u>47N</u> R <u>12W</u>	<u>H13 (same corner)</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Sep 25 2006

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H1) Quarter corner common to Section 3 T46N-R12W and Section 34 T47N-R12W. 1841 - Established by Wm. Burt, Deputy Surveyor: Nest on south side Sec. 34 ...40.00 Birch 30 qr. section corner. Hemlock 30 N45W 33 links. ...80.00 Set post corner Secs. 33 & 34. 1967 - Land corner record of Cleveland-Cliffs Iron Company, signed by T.J. McLaren 10-18-1967 states "set post 1944... from remains of original B.T. Hem. 30 N45W 33 links. New witnesses to corner: Beech 11 N41E 17.0', R.Maple 8 N87E 15.2'." It is not known to the undersigned if these witnesses were made in 1967 or 1944

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H1) The corner tree and accessory were not recovered. The Hemlock OBT was most likely destroyed by road construction, as was the 1944 post and the CCI Beech NBT. Reestablished the corner by single proportionate measurement to the original record, on the Township line and midway between Section corners 2637.41' east and west. From the position thus established, I found a rotting stump, possibly that of the CCI 8" R.Maple NBT at the approximate record bearing and distance.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H1) Set 1" ID I. pipe with 4" alum. MDNR cap. Set measuring nails in:  
 7" Maple N35W 8.58' mrkd "1/4S NBT"  
 7" Y. Birch S72W 38.88' do  
 7" Maple N87E 15.53' do  
 7" Maple S62E 25.7' do  
 Bearings are magnetic. Distances are to nail with MDNR tag.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 12/13/06

For the Michigan Department of Natural Resources, Office of Land and Facilities