

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

| | | |
|--|---------------------------|----------------------------|
| <u>Luce</u> <small>(County)</small> | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>46N</u> R <u>12W</u> | <u>I1</u> |
| | T <u>47N</u> R <u>12W</u> | <u>I13 (square corner)</u> |
| | T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims | | |

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

Aug 31 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I1) Corner common to Sections 2-3 T46N-R12W and Sections 34-35 T47N-R12W. 1841 - Established by Wm. Burt, Deputy Surveyor: West on South side Sec. 35 T47N-R12W ...80.00 Set post corner Secs. 34 & 35. Birch 20 N17E 37 links, Birch 28 N47W 43 links. 1967 - Land corner record of Cleveland-Cliffs Iron Company signed by T.J. McLaren 10-18-1967 states: "Post set from original B.T. Y. Birch 25 N47W 43 links (now down and quite rotten). Set post and 1-1/4" galvanized pipe. New witnesses to corner: Sugar 9 S16W 11.2', Twin R.Maple 4 S41E 17.3'."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I1) Recovered a 1" ID iron pipe in good condition at record bearing and distance from the McLaren NBT twin R.Maple, now 7" DBH in good condition. The original BT birches and the McLaren NBT sugar were not recovered. Accepted the monument as a careful and faithful perpetuation of the position of the original corner. The monument is located 2643.63' west of a perpetuated original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I1) Found a 1" ID iron pipe. Placed a plastic cap stamped "MI DNR PS33986" in it. Set measuring nails in:
 7" twin Maple S33E 17.27' mrkd "S2" *
 7" Maple N63E 6.61' mrkd "S35 NBT"
 7" Maple N43W 23.8' "S34 NBT"
 8" Maple S55W 22.61' "S3 NBT"
 Bearings are magnetic. Distances are to nail with MDNR tag. * denotes McLaren NBT.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 12/13/06

For the Michigan Department of Natural Resources, Office of Land and Facilities