

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>12W</u>	<u>J1</u>
	T <u>47N</u> R <u>12W</u>	<u>J13 (same corner)</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Aug 31 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J1) Quarter corner common to Section 2 T46N-R12W and Section 35 T47N-R12W. 1841 - Established by Wm. Burt, Deputy Surveyor: West on South side Sec. 35 ... 40.00 Set qr. section post. Birch 12 N[omitted]E 15, W.Pine 36 N[omitted]W 25. 1967 - Land corner record of Cleveland-Cliffs Iron Company signed by T.J. McLaren 10-18-1967 states: "Post set from stump of original B.T. W.Pine 36 N [omitted] W 25 links. New witnesses to corner: R.Maple 11 S62W 6.3', B.Cherry 14 N13W 4.6'."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J1) Recovered a 1/2" rebar in a post hole, at record bearing and distance from the witnesses noted in the 1967 record: The R.Maple is now a stump, the B.Cherry is in good condition. Accepted same as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J1) Found 1/2" rebar, drove a 1"IDx36" I.pipe with 4" alum. MDNR cap over it.
 Set measuring nails in:
 11" Maple N66E 18.06' mrkd "1/4S NBT"
 15" Maple S22E 14.44' do
 9" Maple S11W 20.98' do
 16" B.Cherry N07W 4.7' mrkd "1/4S" *
 Bearings are magnetic. Distances are to nail with MDNR tag. * denotes McLaren NBT.



Signed by Stephan J. Szyszkoski Date 12/13/06
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities