

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Luce Co.

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 48 N. R. 8 W.	G-5
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

Filed 6-30 A.D., 1972
 At 4:30 o'clock P.M.
 File No. 63
Doris Taylor, Dep.
 Luce County Reg. of Deeds
 REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on 5/3 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
 Sec. Cor. 9-10-15-16, originally placed by Wells Burt., D.S. 1850.
 Bearings were:
 Sugar 10" N88°W 38 Links
 Sugar 7" S72°E 40 Links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 Found 6" Concrete Post, set by Luce Co. Rd. Commission.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Re-witnessed Corner as perpetuated by Road Commission.
 New Bearings:
 R. Pine 6" S56°W 25.1'
 R. Pine 8" S25°W 47.0'

SIGNED BY *Billy D. Buckler* DATE 6/20/72
 Billy D. Buckler

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:
 SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)