

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Luce Co.

| FOR CORNERS OF-- | LOCATED IN-- | CORNER CODE NUMBER |
|---------------------------------------|---|--------------------|
| 1. PUBLIC LAND SURVEY | T. <u>48</u> N. <u>X</u> , R. <u>8</u> K. <u>W.</u> | A-6 |
| 2. PROPERTY CONTROLLING IN SECTION | T. _____ N. _____, R. _____ E. _____ W. _____ | _____ |
| 3. MISCELLANEOUS PROPERTY IN SECTION | T. _____ N. _____, R. _____ E. _____ W. _____ | _____ |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

Filed 6-30 A.D., 1972
At 4:30 o'clock P.M.
File No. 62
Doris Taylor
Luce County Reg. of Deeds

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 5/3 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
 $\frac{1}{4}$ Cor. on westside, Sec. 18 was originally placed by Wm A. Burt, D.S. in 1840, while running this range line.

Bearings were:
 Beech 14" S7°W 41 Links
 Sugar 16" N17°W 40 Links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 Found Concrete Witness Post set by Luce Co. Road Commission, 50.0' North of Corner location.
 Found another Concrete Post, lying on ground, on North side of road.
 Corner located 5.5' North of center line, M-123.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Re-witnessed corner as perpetuated by Rd. Commission.

New Bearings:
 Maple 8" N15°W 41.5'
 Beech 8" N58°W 45.2'

SIGNED BY *Billy D. Buckler* Billy D. Buckler DATE 6/20/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____