

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 48 N. R. 8 E.	D-5
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

Filed 6-30 A.D., 19 72
 At 3:40 o'clock P.M.
 File No. 53
Doris Taylor My.
 Luce County Reg. of Deeds
 REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 5/1 19 72, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19 _____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
 1/4 Cor. bet. Secs 8-17, originally set by Wells Burt, D.S.
 Bearings were:
 Hemlock 14" S24°E 20 Links
 Hemlock 14" N12°W 3 Links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 Found 6" concrete posts, 50' North and 50' South of Corner, which lies in center of East-west road. Corner monumented by Luce Co. Road Commission.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Re-Witnessed Corner as perpetuated by Road Commission.
 New Bearings:
 Beech 6" N13°W 32.8'
 Maple 8" S25°W 43.3'
 Concrete posts, both North and South of Corner, 50.0' Distant.

SIGNED BY Billy D. Buckler DATE 6/20/72
 Billy D. Buckler
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)
 FOR STATE AND UNITED STATES AGENCIES:
 SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____
 APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)