

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Luce Co.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>48</u> N. S. R. <u>8</u> E. W.	E-13
3. PROPERTY CONTROLLING IN SECTION	T. _____ N. S. R. _____ E. W.	_____
5. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 2/9 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Section Corner bet. Secs: 32-33, on South boundary of Township, set by Wells Burt, D.S. 1850.
Bearings were:
Sugar 14" N83°E 39 lks. and Fir 6" N37°W 6 lks. and
Y. Birch 16" S24°E 21 lks. and Spruce 10" S59°W 31 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Found post at corner, with the N.E. witness, still in place, green with faces completely grown over. Found Y. Birch to S.E., a stump fragment with original scribe marks on lower face. Corner is on North edge of a 22" Soft Maple tree. Tree has been blazed on all four sides.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Placed 1" pipe with 4" aluminium cap at corner.
New Bearings:
17" Cedar S82°W 35.7' and 28" W. Pine S79°E 63.4'

SIGNED BY Billy D. Buckler DATE 3/5/73
SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:
SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____
APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)