

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 48 N.R. 8 W


Luce COUNTY

DESCRIPTION OF CORNER Sec. Corner common to Secs. 5-6-7-8.

CORNER MONUMENT 1" pipe with 4" Aluminum pipe.

DATE MONUMENT PLACED AND WITNESSED 11-13-69

WITNESSES TO CORNER..... 10" CEDAR (S7 NBT) S9°W 9.5'



9" Hemlock (S6 NBT) N25°W 20.0'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner lies $\frac{1}{4}$ chains West of the Northwestern Road.

This corner re-witnessed as placed by H. Lawrence, R.L.S.
Found a large scribed Cedar post in place with several old blazes
facing the corner.

Found remains of a Cedar bearing S45°E, 27 links, this is a probable
witness of record. This position checks well with Sec. Corner and
 $\frac{1}{4}$ Corner to the South.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler* DATE 12-31-69
REGISTERED LAND SURVEYOR