

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

✓

Luce COUNTY


T 48W R 8W

DESCRIPTION OF CORNER ¼ Cor. bet. Secs. 3-10

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 4/12/72

WITNESSES TO CORNER..... 15" W. Pine (¼S NBT) S36°W 123.0'



6" W. Pine (¼S NBT) N8°E 29.4'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This ¼ Corner replaced at a wood post, placed by H. Lawrence, R.L.S. about 1939.

Found no evidence of the ~~two~~ tamarack witnesses, which were considerable distance from the corner.

Found a post with State Park Boundary sign at corner.

Corner lies in an open Spruce marsh 1½ chain North of a Pine ridge.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler* DATE 4/19/72
REGISTERED LAND SURVEYOR

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68