

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 48 N.R. 8W


Luce COUNTY

DESCRIPTION OF CORNER S 1/16 cor. for secs. 21, 22

CORNER MONUMENT 1" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 11/4/65 L. Rubick

WITNESSES TO CORNER..... 14" Sugar (S 1/16)(BT) N05°W, 73 lks.



14" Elm (S 1/16)(BT) S19°W, 29 lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Placed midway and on line bet. sec. cor. to south and $\frac{1}{4}$ cor. to north.

SURVEYOR'S SEAL

SIGNED F. J. Bray DATE 2/6/67
REGISTERED LAND SURVEYOR