

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

2 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 48 N. 8., R. 8 E. W.	D-3
2. PROPERTY CONTROLLING IN SECTION 8_____	T. 48 N. S., R. 8 E. W.	1
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Habbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 9-6 & 9-14, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

D-3 North 1/4 corner of section 8. Wood Post, C.T.'S Beech 8, S63°W, 23 lks,  
Heallock 8, N66°E, 25 lks.

1 West 1/16 corner on north sec. line of section 8. Not prev. est.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

D-3 Corner set at scribed wood post. Remains of heallock blow down in place for original C.T.

1 Corner set M.P.O.L. between the N.W. sec. cor. and the N. 1/4 cor. of sec. 8.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

DNR monument placed at both corners. Bearings:

D-3 12" R. Maple, S27°W, 4.4'	1 Twin 6" Maple, N33°W, 22.6'
6" R. Maple, S52°W, 15.7'	8" Maple, S8°W, 32.9'
6" R. Maple, N26°W, 14.7'	6" Maple, N7°E, 23.6'
8" R. Maple, N83°E, 13.1'	5" Maple, N72°E, 21.4'

SIGNED BY

David B. Habbitt  
David B. Habbitt

DATE 10-10-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)