

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Luce Co.

2 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 48 N. R. 8 E. W.	F-3, E-5
2. PROPERTY CONTROLLING IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David L. Lobbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 9-6 & 9-14, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

F-3 North 1/4 corner of section 9. Wood Post, OLT'S Hemlock 12, S20°E, 20 lks,
Hemlock 8, N65°W, 14 lks.

E-5 SE. section corner of section 8. Wood Post, OLT'S Maple 14, S42°E, 61 lks,
Sugar 8, N30°W, 8 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

F-3 Corner set at scribed wood post. Remains of hemlock stumps in place for both original OLT'S.

E-5 Set on line between the N.E. sec. cor. of section 8 and the stump of a hemlock line tree found on line between sec's. 16 & 17. Distance proportioned to the G.L.O. record which fits very well. The line tree was recorded as S12°E corrected betw. secs. 16-17 4.54 Hemlock 16". A hemlock stump cut 5' high with hack marks and overgrowth very plain on both north and south sides was found in position for this line tree.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-3 DNR Monument. Bearings:	E-5 1" pipe W/Plastic RLS cap buried. Bearings:
10" Cedar, S78°W, 10.15'	Twin 12" R. Pine, S5°E, 28.4'
8" Cedar, S38°W, 8.65'	12" R. Pine, S31°E, 19.1'
6" Cedar, S20°E, 11.4'	12" R. Pine, S46°E, 43.05'
5" Cedar, N39°W, 25.3'	Center line road, North, 14.8'

SIGNED BY

David L. Lobbitt
David L. Lobbitt

DATE 10-10-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)