

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Luce Co.

2 Corners.

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>48</u> N. <u>8</u> E. <u>8</u> W.	<u>E-3</u>
2. PROPERTY CONTROLLING IN SECTION <u>4</u>	, T. <u>48</u> N. <u>8</u> E. <u>8</u> W.	<u>10'</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 9-6, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- E-3 S.W. Section Corner of Section 4. Wood Post, O.T.'S. Hemlock 9, N30°W, 20 lks, Spruce 10, S58°W, 24 lks.
- 10 South 1/16 corner on west side of section 4.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-3 Set by projecting a line from the west 1/4 corner of section 4 across a squared scribed cedar post found at the S. 1/16 corner on the west section line of section 4, and double the distance between them. A cedar post was found lying on the ground near this section corner but it's exact position when standing could not be determined.
- 10 Corner set at scribed wood post M.P.O.L. between W. 1/4 corner and S.W. corner of section 4.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

DNR Monument placed at both corners. Hearings:

- |                             |                              |
|-----------------------------|------------------------------|
| E-3 4" Spruce, S15°W, 39.6' | 10 20" Hemlock, S44°W, 25.6' |
| 7" Spruce, N41°W, 7.6'      | 6" Hemlock, N24°W, 22.8'     |
| 8" Spruce, N68°E, 29.0'     | 16" Hemlock, N32°E, 40.6'    |
| 4" Cedar, S82°E, 33.8'      | 7" Hemlock, S75°E, 22.8'     |

SIGNED BY

David B. Babbitt  
David I. Babbitt

DATE 10-10-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)