

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

2 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>48</u> N. <u>2</u> , R. <u>8</u> E. <u>W.</u>	<u>E-4, C-4</u>
2. PROPERTY CONTROLLING IN SECTION	, T. _____, N. _____, S. _____, R. _____, E. _____, W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION	, T. _____, N. _____, S. _____, R. _____, E. _____, W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David E. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 9-7 & 9-14, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

E-4 East 1/4 corner of section 8. Wood Post, OBT'S W. Pine 8, S45°E, 16 lks.  
Maple 8, N60°W, 10 lks.

C-4 West 1/4 corner of section 8. Corner set by Lilly D. Buckler, L.S. on 5-12-69,  
2" x 60" iron pipe. 14" Aspen, N43°W, 36.1'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

E-4 Corner set M.F.O.L. between NE corner and SE corner of section 8.

C-4 Re-witnessed corner set by Lilly D. Buckler, L.S., 5-12-69.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

DNR monument set at both corners. bearings:

E-4 5" Spruce, S19°E, 54.9'  
5" Spruce, S65°W, 52.0'  
7" Aspen, N05°W, 61.4'  
6" Aspen, N54°E, 73.1'

C-4 Twin 8" W. Pine, S35°W, 56.2'  
14" Aspen, N43°W, 36.1'  
4" Maple, N52°E, 18.2'  
Center Road, East, 40.0'

SIGNED BY

David E. Babbitt  
David E. Babbitt

DATE 9-21-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)