

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Luce Co.

3 Corners

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>48</u> N. S., R. <u>8</u> E. W.	<u>C-7, D-7, E-6</u>
2. PROPERTY CONTROLLING IN SECTION_____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 6-18 & 28, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

C-7 SE section corner of sec. 18. Wood Post. OBT'S: Sugar 9, S17°E, 33 lks  
Beech 9, N74°W, 19 lks.  
D-7 South 1/4 corner of sec. 17. Wood Post. OBT'S: Fir 9, N40°W, 20 lks  
Beech 9, S20°E, 24 lks.  
E-6 East 1/4 corner of sec. 17. Wood Post. OBT'S: Cedar 12, N55°E, 41 lks  
Spruce 9, S35°W 14 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

C-7 Corner set by Double Proportionate measure between section corners 1 mile North, East, and West and ¼ corner ½ mile south.  
D-7 Corner set by Single Proportionate measure between section corners East and West.  
E-6 Corner set M.P.O.L. between the N.E. section corner and S.E. section corner of section 17.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D.N.R. Monument set at all three corners. Bearings are:

C-7	6"H. Maple, S62°W, 9.65'	D-7	10"H. Maple, N57°E, 31.2'	E-6	8" Spruce, S53°E, 57.2'
	5"H. Maple, N77°W, 15.90'		6"H. Maple, S33°E, 12.7'		6" Spruce, S6°E, 28.4'
	14"H. Maple, N62°E, 17.40'		8"H. Maple, S30°W, 3.7'		5" Spruce, N88°W, 21.2'
	8"R. Maple, S37°E, 5.50'		8" Hemlock, N23°W, 22.8'		8" Aspen, N36°E, 40.0'

SIGNED BY

Gerald L. Wiggins

DATE 8-29-84

SURVEYOR'S MICHIGAN REGISTRATION NO.

23521

