

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Luce Co.

2 Corners

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>48</u> <sup>N.</sup> S., R. <u>8</u> <sup>W.</sup>	<u>C-6, B-7</u>
2. PROPERTY CONTROLL- ING IN SECTION_____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 6-18 & 6-20, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- C-6 East 1/4 Corner of Section 18. Wood Post. OBT'S: Sugar 10, N40<sup>0</sup>W, 13 lks.  
Beech 10, S55<sup>0</sup>E, 26 lks.
- B-7 South 1/4 Corner of Section 18. Wood Post. OBT'S: Sugar 12, N10<sup>0</sup>W, 14 lks.  
Beech 9, S05<sup>0</sup>E, 22 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-6 Corner set by single proportionate measure between section corners North and South.
- B-7 Corner set by single proportionate measure between section corners East and West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

DNR Monument placed at corners. Bearings are:

- |     |                                        |     |                                         |
|-----|----------------------------------------|-----|-----------------------------------------|
| C-6 | 7" H. Maple, S32 <sup>0</sup> E, 31.8' | B-7 | 7" H. Maple, S50 <sup>0</sup> E, 0.9'   |
|     | 7" H. Maple, S07 <sup>0</sup> E, 41.3' |     | 8" H. Maple, S18 <sup>0</sup> W, 22.8'  |
|     | 7" H. Maple, S71 <sup>0</sup> W, 20.7' |     | 12" H. Maple, N66 <sup>0</sup> W, 23.4' |
|     | 14" Beech, N35 <sup>0</sup> E, 22.2'   |     | 6" H. Maple, N15 <sup>0</sup> E, 9.8'   |

SIGNED BY

Gerald L. Wiggins  
Gerald L. Wiggins

DATE 7-20-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

