

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>LUCE</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>8W</u>	<u>K-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Gerald L. Wiggins in a field survey on 10-2, 19 90
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as
 expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

S.W. Section Corner of Section 1. OBT'S: Beech 8", N56°E, 19 lks. & Beech 5", S45°W, 8 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Set corner at intersection of N-S and E-W old blazed lines. Corner set 133.6' south of center
 line M-123 as shown on road construction plans and M.D.O.T. right of way plans. Distance South
 to river fits original, as well as distance East to original meander corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

DNR monument placed at corner. 28" Hemlock, S05°E, 56.8'
 10" Hemlock, N65°W, 39.92'
 14" Beech, N60°E, 38.15'
 20" Spruce, S36°W, 25.0'

Signed by Gerald L. Wiggins Date 2-26-90
 Surveyor's Michigan License No. 23521

