

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 8W	E7
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 03/19/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E7) Corner common to Sections 16-17-20-21. 1850 - Established by Wells Burt, Deputy Surveyor. Set spruce post. Cedar 11" N25E 10 links, Cedar 10" S16W 22 links. 1965 - Remonumented by F.J.Bray RLS: "This corner was set at scribed wood post set by Harold Lawrence. Cedar line tree checks to north. Point of older post found. Corner lies in north margin of beaver flooding". Set 1" iron pipe with 4" alum. cap. 12" Spruce N20E 11 links, 11" Cedar S70E 46 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E7) Found the 1965 monument, submerged in a beaver flooding, leaning heavily to the south, adjacent to what is possibly the remains of a wood post. Plumbed the monument to be in accord with the remaining 1965 NBT - 11" Cedar SE, now a rotting stump. The 12" Spruce NBT was not recovered. Accepted the monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E7) Fd. 1" ID I. pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 12" Cedar S78E 24.25' mrkd "S21 NBT"
 4" Balsam N32E 6.75' "S16 NBT"
 10" Cedar S72W 16.2' "S20 NBT"
 5" Cedar N54W 25.1' "S17 NBT"
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 05/11/2009
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities