

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 48N R 8W	E8
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 03/30/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E8) Quarter corner common to Sections 20 and 21. 1850 - Established by Wells Burt, Deputy Surveyor, midway and on the Section line between Section corners 39.97 chains north and south. Set Maple post. Cedar 12" S56W 28 links, Cedar 10" S36E 10 links. 1965 - Remonumented by F.J.Bray RLS "at scribed post set by Harold Lawrence which checks with original BT (Cedar 12" S56W 28 links) now stub with scribe marks on lower face visible". Set 1" iron pipe with 4" aluminum cap. 12" Hemlock N73W 18.5 links, 7" Cedar N43E 13.5 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E8) Found the 1965 monument in good condition and at record bearing and distance from the Cedar NBT NE, in good condition. Any evidence of the Hemlock NBT NW and the original BTs was obscured by snow cover this date. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E8) Fd. 1" ID I.pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:

- 10" Cedar S72E 23.3' mrkd "1/4S NBT"
- 10" Cedar N45E 9.0' "1/4S" 1965 NBT
- 6" Maple S15E 1.9' mrkd "1/4S NBT"
- 16" Cedar N69W 25.55' do

Bearings are magnetic.



Signed by *Stephan J. Szyszkoski* Date 05/11/2009
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities